


NOTES:


1. SUB-BASE DEPTH AND PREPARATION IS DEPENDENT ON SITE CONDITIONS PLUS LOADING REQUIREMENTS.
2. TRUEGRID PRO PLUS PRODUCTS ARE SUFFICIENTLY RATED 20.0 T AXLE RANGING FROM SINGLE TYRE TO TRIPLE AXLE DUAL TYRE.
3. TYPICAL SEEDING OR HYDROSEEDING METHODS FOR GRASS GROWTH ARE ACCEPTABLE WITH TRUEGRID.
4. SOD CAN BE LAID ON SOIL FILLED GRID FOR IMMEDIATE GRASS (TYPICAL FOR FIRE LANES)
5. FOR HIGHER TRAFFIC SOD INSTALLATIONS, RECESS SOIL LEVEL WITHIN TRUEGRID AND PRESS IN SOD SO THAT TOP OF GRID IS AT SOIL LEVEL.
6. GEOGRID MESH OR GEOFABRIC MAY BE REQUIRED BETWEEN SUBGRADE & SUBBASE FOR CERTAIN SOILS AND SITE SPECIFIC REQUIREMENTS.
7. FILTER FABRIC MAY BE REQUIRED BETWEEN TRUEGRID AND SUB-BASE MATERIAL IF HIGH VOID RATIO IN SUB-BASE MATERIAL.
8. NO STAKING NECESSARY WITH TRUEGRID PRO PLUS WHEN SLOPE IS BELOW 20 DEGREES. ASSESS PROJECT, AS NEEDED.
9. TRUEGRID PRO PLUS IS ADA COMPLIANT WITH PROPER FILL MATERIAL.
10. FINAL ENGINEERED CROSS SECTION AGGREGATES AND DEPTH SHOULD ALLOW FOR EXPECTED INFILTRATION RATES, STORAGE CAPACITIES, OUTLET FLOW RATES, AND OTHER SITE SPECIFIC CONDITIONS AND LOAD REQUIREMENTS.
11. THIS CROSS SECTION IS FOR INFORMATION ONLY.



Individual Grid size is 610mm by 610mm
The pieces lock together using Male / Female inbuilt clips.

ADJOINING FINISH GRADE TRUEGRID SURFACE FLUSH OR SLIGHTLY RECESSED SEE DRAWING TG-EDGE-OPTS FOR EDGING OPTIONS

SUB-BASE:
19.1mm OR 25.4mm CLEAN, WASHED ANGULAR STONE FOR DETENTION CONSIDERATIONS. i.e. #57 STONE (SEE NOTE #7). OR A COMPACTED GRAVEL / SANDY ROAD BASE. OR A II TYPE ROAD BASE, COMPACTED WHEN NO DETENTION OR HEAVY DRAINAGE NEEDED.



TRUEGRIDPAVER.COM.AU
1 300 796 018

GRASS FILL MEDIUM LOAD TRUEGRID PRO PLUS

APPLICATION:

PARKING LOT, RV PARKING,
PARKING PADS, DRIVEWAYS



CLIENT / PROJECT

UNLESS OTHERWISE SPECIFIED:
DIMENSIONS ARE IN INCHES

PROPRIETARY DESIGN RIGHTS NOTICE:
THIS DESIGN WAS ORIGINATED BY AND IS
THE EXCLUSIVE PROPERTY OF TRUEGRID.
IT IS DISCLOSED IN CONFIDENCE
WITH THE UNDERSTANDING THAT NO
REPRODUCTION OR OTHER USE OF THE
INFORMATION IS AUTHORIZED WITHOUT
SPECIFIC AGREEMENT IN WRITING BY
TRUEGRID.

APPROVAL INFORMATION

DRAWN BY:	DATE:
J. Thehy	2/18/2019
CHECKED BY:	DATE:
J. Thehy	2/18/2019
APPROVED BY:	DATE:
C. White	2/18/2019
WEIGHT:	



TRUEGRID GRASS
FILL INSTALLATION
MEDIUM LOAD

00	ORIGINAL ISSUE	JT	JT	CW	01/31/2019
REV		DRAWN	CHECKED	APPROVED	DATE
REVISION					

DO NOT SCALE DRAWING

SIZE	D	DRAWING NUMBER	TG-AU-GRS-ML	REV	00
SCALE	1:1.5	SHEET	1 OF 1		